



United States
Department of
Agriculture

Forest Service
Northern Region
Engineering



Cost Estimating Guide for Road Construction

Internet:

www.fs.fed.us/r1

February 2004

This page intentionally left blank for duplexing purposes.

COST ESTIMATING GUIDE FOR ROAD CONSTRUCTION

March 2004

TABLE OF CONTENTS

SECTION	SECTION TITLE	PAGE
	GENERAL INFORMATION 2/2004	
	Table of Weights and Measures	6
	General Information and Instructions.....	8
	ENGINEER'S ESTIMATE 2/2004	
	Engineer's Estimate.....	14
	DAVIS-BACON/PURCHASER WAGE RATE ADJUSTMENT	
	Davis-Bacon/Purchaser Wage Rate Adjustments.....	18
	Time Estimates & Calculation of Midpoint of Construction.....	20
	PROJECT REQUIREMENTS 2/2004	
151/160	Mobilization	28
152/170-180	Construction Survey and Staking.....	28
153/160	Contractor Quality Control.....	32
154/160	Contractor Sampling and Testing.....	32
156	Public traffic.....	34
157/204	Soil Erosion Control.....	34
160/207	Develop Water Supply and Watering.....	37
	CLEARING AND EARTHWORK 2/2004	
201	Clearing and Grubbing.....	40
202	Additional Clearing and Grubbing.....	40
	Figure 201-1 Clearing and Grubbing.....	43
	Figure 201-2 Equivalent Volume Using Diameters and Spacing	44
	Brushing.....	45
203/202	Removal of Structures and Obstructions.....	46
204/203	Excavation and Embankment.....	46
208/206	Structure Excavation and Backfill for Selected Major Structures.....	55
211/210	Roadway Obliteration.....	55
212/299	Linear Grading.....	56
	SLOPE REINFORCEMENT AND RETAINING WALLS	
251/619	Riprap.....	66
253/630	Gabions and Revet Mattresses.....	66
255/613	Mechanically – Stabilized Earth Walls.....	66
257/631	Alternate Retaining Walls.....	67
	AGGREGATE COURSES 2/2004	
301/304	Aggregate Courses.....	70
303/306	Road Reconditioning.....	75
306/412	Dust Palliative.....	76
321	Road Surface Stabilization.....	76
	ASPHALT PAVEMENT AND DUST PALLIATIVE 2/2004	
400	Asphalt Pavements - General	78
403	Hot Asphalt Concrete Pavement.....	78
410	Slurry Seal.....	78

411/408	Asphalt Prime Coat.....	78
412/407	Asphalt Tack Coat	78
414	Asphalt Pavement Crack and Joint Sealing.....	78
415	Paving Geotextiles.....	78
430/410	Asphalt Surface Treatments.....	79
431/417	Seal for Light Traffic Pavements.....	83
432	Asphalt Pavement Patching.....	83
BRIDGE CONSTRUCTION 2/2004		
551	Driven Piles.....	86
552	Structural Concrete.....	86
553	Prestressed Concrete	86
554	Reinforcing Steel.....	86
555	Steel Structures.....	86
556	Bridge Railing.....	86
557	Timber Structures	87
DRAINAGE AND INCIDENTAL CONSTRUCTION 2/2004		
601/602	Minor Concrete Structures.....	90
602/603	Culverts and Drains.....	90
603/617	Structural Plate Structures.....	93
604	Manholes, Inlets and Catch Basins.....	93
605/209	Underdrains, Sheet drains, and Pavement Edge Drains.....	94
606/621	Corrugated Metal Spillways	94
607/618	Cleaning, Reconditioning, & Repairing Existing Drainage Structures...	95
609/608	Curb and Gutter.....	95
615/609	Sidewalks, Drive Pads, and Paved Medians.....	95
617/606	Guardrail.....	95
618/606	Concrete Barriers and Precast Guardwalls.....	95
619/607	Fences, Gates and Cattle Guards.....	96
621/623	Monuments and Markers.....	96
622/637	Rental Equipment.....	96
624	Topsoil.....	103
625	Turf Establishment.....	103
629	Rolled Erosion Control Products & Cellular Confinement Systems....	103
633	Permanent Traffic Control.....	103
634	Permanent Pavement Markings.....	104
640	Road Closure Devices.....	104
641/611	Development of Pits and Quarries.....	104
660	Geocell Abutment Stabilization.....	104
LABOR RATES 2/2004		
	Labor Rates.....	106
TEMPORARY ROAD COST ESTIMATING 2/2004		
	Cost Estimating for Temporary Roads.....	108
BID HISTORY 2/2004		
	Summary of Bid History.....	118
	Bid History.....	119
	End of Document	127